




A wholly owned subsidiary of Infiltrator Water Technologies, LLC



WHITEWATER[®] DF SERIES AEROBIC RESIDENTIAL WASTEWATER TREATMENT SYSTEM

INSTALLATION, OPERATION AND MAINTENANCE MANUAL



WARNING! Failure to properly secure the top may result in a serious health or safety hazard.

DISTRIBUTOR AND HOMEOWNER NOTES

1. The Delta Treatment Systems Water Model DF40-M has been tested by NSF International and conforms to NSF/ANSI Standard #40, class 1 effluent requirements. All other DF series models are certified based on provisions in the standard for certification of a series of plants of the same model varying only in rated treatment capacity and materials of construction.
2. State and/or local regulations govern the installation and use of individual Aerobic Wastewater Treatment Systems and must be complied with.

Consult your local Sanitarian/Environmentalist prior to installation.

HOMEOWNER RECORDS

S/N: _____ DATE: _____

INSTALLED BY: _____

DISTRIBUTOR: _____

NOTICE

This booklet provides operations, installation and warranty information on the **TREATMENT PLANT ONLY**. Other components that you may have, such as dosing equipment, drip irrigation or other components, require additional operations booklets and carry separate warranties.

Be sure that you have all of the correct booklets for each of the component pieces in your system.

Contact your installer or call 1-800-219-9183.

DELTA TREATMENT SYSTEMS	
QUALITY ASSURANCE TAG	
S/N _____	DATE _____
Fiberglass Integrity: Barcol Tested Thickness Verified Clarifier Solid	_____
	(Initial)
Water Tested	_____
	(Initial)
Metal Integrity: Welds Inspected Paint Adherence Clips/Brackets Intact	_____
	(Initial)
Compressor Package Complete:	_____
	(Initial)
Internal Assembly: Clarifier Intact Air Header Complete and Secured Air Droplines Complete and Secured Discharge Tee Assy. Center and Level Cover Attached, Sealed and Secured	_____
	(Initial)
Component Kit: Air Header Complete and Secured Air Droplines Complete and Secured Discharge Tee Assy. Secured	_____
	(Initial)

Post in a service/utility area

WHITEWATER[®] TREATMENT SYSTEMS NOTICE

This home is served by an individual wastewater treatment system. This system will serve you well only if it is properly maintained. Your system comprises of _____.

Your system is located _____.

You should not build or fill over this area, or allow heavy traffic. Do not allow water to stand over this area. Avoid using strong chemicals, cleaning fluids, etc., which will kill helpful bacteria in the system. You should also avoid flushing grease, food scraps, cigarette butts, sanitary napkins and other inorganic waste down the drain.

You should have your system serviced (pumped out) every three to five years. Your service technician can advise you if you need more frequent or additional service.

To have your system serviced, or for additional information, contact _____ at _____.

All of the details regarding system operation can be found in your homeowner's manual, which you should have received at installation. If you did not receive a copy, call 1-800-219-9183 and we will send you one at no charge.

Keep a Record of Service Below:

DATE	SERVICE PERFORMED	SERVICE TECHNICIAN

A WORD ABOUT YOUR DELTA TREATMENT SYSTEMS AEROBIC WASTEWATER TREATMENT SYSTEM AND HOW IT WORKS

The Whitewater® Aerobic Wastewater Treatment System that you have purchased produces high quality water suitable for various disposal methods. It is used to enhance your on-site wastewater disposal system. You can be proud that in purchasing your Whitewater System with a minimum amount of maintenance, you can directly contribute to a cleaner, safer environment.

All wastewater treatment systems of this type work by using the bacteria that nature has provided. By pumping air into the system, the bacteria grow and thrive in much larger amounts than would occur naturally. The over-population of bacteria speeds up the process of breaking down domestic wastewater, making it safe to release into the environment. This entire process takes place within the walls of your specially designed, self-contained Whitewater Treatment System.

Your Whitewater System is made up of an outer mixing chamber and center settling chamber. Raw unsettled domestic wastewater enters directly into the mixing chamber. Mixing is accomplished by air passing from the air pump to the air droplines located around the outer wall of the mixing chamber. The design is such that solids remain in suspension with a general flow pattern up the outer plant wall, then down the outside of the settling chamber when the air pump is on. This flow pattern allows a quiet condition in the settling chamber.

The mixed liquid enters the hopper-shaped settling chamber at the bottom and travels upward toward the discharge pipe. The quiet condition allows solids to settle down and re-enter the mixing chamber.

The result of this process is a clear, odorless discharge, which meets or exceeds state water quality standards.

By following the few simple steps that you find in this manual, your Whitewater System will provide you with years of service and the knowledge that you are doing your part to protect our groundwater, lakes, rivers and streams.

Whitewater is a registered trademark of Delta Treatment Systems, LLC,
a wholly owned subsidiary of Infiltrator Water Technologies

HOMEOWNER CARE AND SERVICE PROVIDER INSTRUCTIONS

The Whitewater[®] System has been designed and built to provide long term, reliable and efficient service.

Once the unit has been installed (see installation instructions), the unit will operate with a minimum amount of attention.

Please reference the system's data plates that are located on the aerobic tank 24" cover, air pump and the alarm panel in the event that a problem arises or service is required. Call 1-800-219-9183 for your local service provider.

The following should be accomplished as checks for system failure:

Daily

- Observe the warning device, which comes on when the power to the air pump has been interrupted or when the air supply system has malfunctioned. If the alarm is activated, check for a blown fuse or thrown circuit breaker. Check air pump to be sure it is operating. Once accustomed to the soft humming sound of a properly operating unit, any unusual noise is an indication of malfunction. If an unusual noise is detected or total failure is observed, call an authorized Delta Treatment Systems dealer/distributor.

Weekly

- Check the treatment plant for offensive odor. If such a condition should develop, call an authorized Delta Treatment Systems dealer/distributor.

Every Three Months

- **The air filter on the air pump should be cleaned.** Rinse with warm water if necessary. (See installation instructions.) Do not use oil or other solvents.

Every Six Months

- Clean air filter on the air pump
- Inspect and make any necessary adjustments to mechanical and electrical components.
 - Make sure all components are functioning properly (alarms, switches, air pump, etc.).
- Inspect the color and turbidity of the effluent and check for any odor.
 - No offensive odors should be present; an earthy odor is typical.
- Take a sample from the aeration tank and perform a 30-minute settle ability test described in the "Solids Removal" section.
- Break up any sludge that may have developed in the clarifier so it can return to the aeration zone. Care should be taken to prevent solids from leaving the unit.
- **The homeowner must be notified in writing if any improper operation is observed and cannot be corrected at the time of service.**
- **Refer to "Troubleshooting Guide" section in this manual.**

Note: To keep maintenance to a minimum and ensure high effluent quality, see the section labeled "The following should NOT be used or discarded into the system".

THE FOLLOWING SHOULD NOT BE USED OR DISCARDED INTO THE SYSTEM

- Greases, fats, oils, pesticides, herbicides or any other toxins.
- Garbage disposal should be used sparingly. Discard of food waste, grease, etc., in the solid waste bin. Food waste represents additional matter the Fixed Film Wastewater Treatment System would have to digest, increasing pump-out intervals.
- Paints, household chemicals, automobile fluids and mop water should not be put into the system.
- Nonbiodegradable items such as cigarette butts, disposable diapers, feminine hygiene products, condoms, hair, coffee grounds, rags, paper towels, bandages, latex, plastic or metallic objects, etc. should not be put into the system.
- Laundry loads must be spread out over the week. Once a week multiple loads or half loads are not recommended.
- Citrus products, oranges, lemons, grapefruit, etc. should not be put into the system.
- Additives for septic systems do more harm than good.
- Hydraulic overload due to excessive water from other sources.
- Home brewery waste, strong medicines, antibiotics and antibacterial soaps should be avoided.
- Strong disinfectants or bleaches. Laundry products such as Lysol, Pine-Sol, Tidy Bowl or discharge from water softeners.
- Recommended detergents are powdered, low-sudsing, low phosphates and biodegradable washing soda ingredients such as Gain, Arm & Hammer, Fresh Start and Dash Bright. Fabric softener dryer sheets are also recommended.
- Recommended cleaning products are nonchlorine, biodegradable and nontoxic such as Ivory and Sunlight dish washing liquids, Cascade and Sunlight powdered dishwasher detergents, Comet and Biz powdered cleaners and baking soda.

Systems requiring pump-outs due to the above violations are not covered by the warranty.

The Whitewater[®] System is designed to handle domestic wastewater, and nothing else should go into it. For anything other than domestic wastewater contact Delta Treatment Systems.

WARNINGS

- The proper operation of this or any other home sewage system depends upon proper organic loading and the life of the microorganisms inside the system. Delta Treatment Systems is not responsible for the in-field operation of a system, other than the mechanical and structural workings of the plant itself. We cannot control the amount of harsh chemicals or other harmful substances that may be discharged into the system by the occupants of a household. We can only provide a comprehensive owner's manual that outlines substances that should be kept out of the system.
- Hydraulic overloading (flows in excess of design flow) may cause the sewage treatment system not to perform to the fullest capabilities.
- Ants have been shown to be destructive to the air pump. Regular care should be taken to prevent infestation of ants near the system. Damage or destruction by ants is not covered under manufacturer's warranty.
- Your state or local health department may require other pieces of equipment to function separately or in conjunction with equipment manufactured by Delta Treatment Systems is not responsible for the mechanical or electrical safety of equipment it does not manufacture or supply with its aerobic treatment units. Particular care should be used in evaluating the electrical or mechanical safety of equipment manufactured by others. This may include but not be limited to electrical control panels or air pumps.
- If electrical service has not been installed for checking the air distribution system during installation, and if an extension cord is used to test the air pump, NEVER leave the extension cord plugged in. Remove it after testing is completed.
- Due to a possible fire hazard, DO NOT plug into service equipment on power pole and DO NOT use extension cords. All electrical work performed by the installer or others must be in accordance with the National Electrical Code (NEC) and local codes.
- The operation and maintenance outlined in this manual applies to normal operating conditions. Extreme conditions such as frigid cold temperature, extreme heat and high altitudes may affect the operation and maintenance of this unit. Consult factory regarding these extreme conditions.

California Proposition 65 Warning

⚠ WARNING This product contains chemicals known to the State of California to cause cancer or birth defects or other reproductive harm.

WARNING

Failure to Properly Secure the Top May Result in a Serious Health or Safety Hazard.

SOLIDS REMOVAL

The Whitewater® Treatment System is designed to provide years of trouble-free operation.

Determination of the need for solids removal can be done through a simple test. A one-quart sample should be pulled from the aeration tank and can be done so through the 4" sample port. Allow the sample to settle in a clear one-quart jar for thirty minutes. If the solids content exceeds 60% of the total volume after settling, the treatment plant should be pumped out. Call your local authorized sewage disposal service to have the tank contents pumped out and disposed of properly.

The method of pumping out should be as follows:

- Remove any floating solids by skimming.
- The air pump must be operating to keep the solids in suspension.
- Pump out two-thirds of the tank volume with the suction pipe opening being placed at the tank bottom.

After the pump-out process is complete, fill the tank with fresh water to normal operating level.

Refer to the Installation Instructions to get the treatment plant back into operation.

Should indication of improper operation be observed at any time, contact your local authorized Delta Treatment Systems dealer/distributor.

Note: The cost associated with pumping the treatment system is not covered under warranty and is not included in the service policy.

SEASONAL USE GUIDELINES OF THE WHITEWATER[®] AEROBIC TREATMENT SYSTEM

These guidelines are for conditions as outlined below and apply for systems that are not in use for periods of time indicated. Site conditions not covered by the following must be forwarded to Delta Treatment Systems for recommended guidelines to meet the particular site conditions.

1. System not in use for more than one month and less than three months. Electrical power is left on and there are no frost conditions.
 - Leave air pump on and system running.
2. System not in use more than three months. Electrical power is turned off and there are not frost conditions.
 - While system is operating with the air pump on, remove all material and liquid from tank.
 - Refill with clean water.
 - Turn off air pump.
3. System not in use more than three months. Electrical power is on and there are not frost conditions.
 - Leave air pump on and system running; OR
 - While system is operating with the air pump on, remove all material and liquid from tank.
 - Refill with clean water.
 - Turn off air pump.
4. System not in use. Electrical power is turned off and there are frost conditions.
 - While system is operating with the air pump on, remove all material and liquid from tank.
 - Turn off air pump.
 - If high groundwater is present, fill with clean water.
 - If no groundwater is present, leave tank empty.

Under no circumstances should the air pump be turned off for more than a few days without removing tank contents!

SAMPLING REQUIREMENTS

A Whitewater® aerobic treatment plant properly operated and maintained should provide the following effluent quality of:

Carbonaceous Biochemical Oxygen Demand 5 day average (CBOD5) of	less than 25 mg/l (or ppm),
Suspended Solids (SS) of	less than 30 mg/l (or ppm),
Volatile Suspended Solids of	less than 30 mg/l (or ppm).
pH of	6.0 to 9.0
Dissolved Oxygen	1.5 to 3.0 mg/l (or ppm)

Taking Effluent Samples:

Samples must be taken in the effluent discharge line or an effluent pump or after the chlorine contact tank. We recommend allowing the effluent to flow through the discharge pipe for a minimum of two minutes before taking the sample. This will allow any solids to be flushed out that might have accumulated in the discharge pipe. Please find attached drawing of a Sample Port.

Sampling should be taken by a local certified testing laboratory or by following their procedures. The following recommended guidelines may be used if local procedures are not available:

Carbonaceous Biochemical Oxygen Demand (CBOD)

Samples for CBOD analysis may degrade significantly during storage between collection and analysis, resulting in low CBOD values. Minimize reduction of CBOD by analyzing the sample promptly or by cooling it to near-freezing temperature during storage. However, even at low temperature, keep the holding time to a minimum. Warm the chilled samples to 20°C before analysis; some storage time can be used to accomplish this conveniently.

- **Grab Samples:** If analysis is begun within two hours of collection, cooling is unnecessary. If analysis is not started within two hours of sample collection, keep sample at or below 4°C from the time of collection. Begin analysis within 6 hours of collection; when this is not possible because the sampling site is distant from the laboratory, store at or below 4°C and report length and temperature of storage to the lab. Never start analysis more than 24 hours after grab sample collection. When samples are to be used for regulatory purposes, make every effort to deliver samples for analysis within six hours of collection.

Total Suspended Solids (TSS)

Use resistant glass or plastic bottles, provided that the material in suspension does not adhere to container walls. Begin analysis as soon as possible because of the impracticality of preserving the sample. Refrigerate sample at 4°C to minimize microbiological decomposition of solids.

Phosphorus

If phosphorous forms are to be differentiated, filter samples immediately after collection. Preserve by freezing at or below -10°C . Add 40 mg HgCl_2/L to the samples, especially when they are to be stored for long periods. Do not add either acid or 2CHCl_3 as a preservative when phosphorous

forms are to be determined. If total phosphorus alone is to be determined, add 1 mL concentration HCL or freeze without any additions.

Do not store samples containing low concentrations of phosphorus in plastic bottles unless kept in a frozen state because phosphates may be adsorbed onto the walls of plastic bottles.


Rinse all glass containers with hot diluted HCL, then rinse several times in distilled water. Never use commercial detergents containing phosphate for cleaning glassware used in phosphate analysis.

Ammonia Nitrogen




Most reliable results are obtained on fresh samples. Destroy residual chlorine immediately after sample collection to prevent its reaction with ammonia. If prompt analysis is impossible, preserve samples with 0.8 mL concentration $\text{H}_2\text{SO}_4/\text{L}$ sample and store at 4°C . The pH of the acid-preserved samples should be between 1.5 and 2. Some wastewater may require more concentration H_2SO_4 to achieve this pH. If acid preservation is used, neutralize samples with NaOH or KOH immediately before making the determination.

SAMPLE PROCEDURES:

1. PRIOR TO TAKING SAMPLE HAVE WHITEWATER PLANT DISCHARGE EFFLUENT FOR UP TO 4 MINUTES BY FLUSHING TOILETS AND/OR USE GARDEN HOSE TO FLUSH OUT SAMPLE PORT.
2. INSERT SAMPLE COLLECTING BOTTLE TO COLLECT ONLY EFFLUENT WHICH IS CASCADING OVER THE CASCADING EDGE.
3. HANDLE, STORE AND TRANSPORT SAMPLES AS SPECIFIED BY POLICIES AND PROCEDURES PROVIDED BY THE TESTING LABORATORIES.



EXAMPLES OF SAMPLE PORTS



SAMPLE PORTS

DWN BY:
B.LANDRY

DATE:
06/24/03

SCALE:
N.T.S.

DWG. NO.:
CRT361

INSTALLATION INSTRUCTIONS

ONLY FOR USE BY CERTIFIED, LICENSED INSTALLER

1. **Care must be taken offloading and unpacking components. Care must be taken not to damage fiberglass with forklift or any other offloading device. Check for any damaged components that may have happened in transportation and notify factory within 24 hours of delivery.** Prepare an excavation, having a diameter approximately one foot larger than the tank and a depth that will allow approximately 3 inches of the inspection port to extend above normal ground level. Backfill with a 6-inch layer of sand or gravel if otherwise unable to provide a smooth, level, compact base. We recommend that the hole be roped off in some fashion to prevent injury to passersby.
2. Using lifting lugs provided, place the plant in the excavation so that the inlet and outlet line up with the sewer piping. The inlet line should slope down toward the plant and the outlet line should slope down away from the plant. The plant should be level within 1/2 inch, edge to edge.
3. Position inlet and outlet lines and make connections as necessary, depending upon the construction materials. The inlet line should be inserted and glued into the inlet elbow and the discharge line should be inserted and glued into the outlet coupling.
Note: Open inspection port and make sure discharge tee assembly is level and centered in clarifier prior to attaching discharge piping. Fill the tank with water until water flows from the discharge before backfilling. Back fill around the treatment plant up to the bottom of the discharge connections.
4. Do not install the air pump(s) in a low-lying area where water may accumulate. The air pump should be installed near the control panel and within 100 ft. of the tank. The air pump can be installed outdoors or in a clean, well-ventilated area, such as a tool room, garage, etc. **If the linear air pump is to be installed in an additional enclosure, the enclosure must be approved by Delta Treatment Systems® in writing.**
5. Mount the control panel in an area such that the alarm can be heard and be readily observed. A 3-wire grounded GFI circuit is required for safety. Install a disconnect switch near the panel to visually disconnect the control panel from the power source. All electrical work shall be done according to NEC and local code requirements. The control panel must be grounded. Connect the source ground wire to the ground location in the panel.
6. The control panel is rated for indoor and outdoor use and contains a fuse for the air pump. An electrical malfunction in the air pump or wiring to the air pump will cause the fuse to blow. The control panel also contains a pressure switch with a visual and audible alarm. Loss of air pressure caused by air pump system malfunction or a high water level in the treatment plant will cause the alarm to sound and light to illuminate.

7. Attach control panel to suitable mounting surface using all four mounting holes on back of box. Use proper screws of sufficient length to ensure a secure and permanent mounting.
8. Control panel is rated for outdoor service; however, do not place it where it can be immersed in rising water or where run-off water such as from a roof will fall on it. Do not mount it where it is subject to wetting from sprinklers, hoses, etc.
9. The control panel must never be connected to a circuit that is not properly grounded. Never connect the unit to a nongrounded circuit. If there is doubt, have a qualified electrician check for proper grounding. The control panel must be connected to a 20 amp maximum electric source equipped with a ground fault interrupter (GFI) circuit breaker. A standard circuit breaker can be replaced with a GFI circuit breaker, which can be obtained from almost any store that sells electrical supplies.
10. After the control panel is properly mounted, connect conduit and install wiring as shown on drawings bound herein.
11. Install the float switch wire from the control panel to the treatment plant. Wire can be direct burial type UF 600 volt or can be installed in schedule 40 pvc conduit. Use type THWN, 600 volt if installed in conduit. Wire must be buried in accordance with NEC table 300-5. If in doubt, bury 24" deep. Keep sufficient distance or depth from airline to avoid confusion of pipes or damage to wiring during installation or repair of air piping. Connect to the float switch normally open contacts using underground rated compound filled wire nuts.
12. If using the CP22 panel, ignore #11. To set the high level pressure switch that detects high water level in the unit, follow the instructions below:

Bring plant to operating water level with compressor turned on. Using properly sized screwdriver, turn high-level alarm adjustment screw clockwise until alarm occurs. Then turn the screw counterclockwise until alarm stops. (See "high level pressure setting" drawing in this manual.)
13. Connect the pressure air tubing to the 1/8" barb-fitting directly to the 3/4" airline or directly to the compressor. Refer to illustrations in Appendix B for appropriate air tubing connections.
14. Install 3/4" schedule 40 PVC piping between air pump and treatment unit. A minimum of 12" ground cover is recommended.
15. Turn power on to control panel. Air pump should start.
16. Check air piping joints for leakage using a soapy water solution. Repair if necessary and then carefully backfill air line and inlet and discharge piping and cover plant to grade level.
17. Recheck water level in the tank.
18. Plant is ready to receive incoming sewage. No special start-up procedures are required. The process is naturally occurring and does not require any special additives.


19. Test alarm circuit by momentarily squeezing air tubing and allowing air pressure to decrease. This should take a few minutes. Alarm should occur. Release air tubing and alarm should stop. Lift float in tank to horizontal position. Alarm should occur. Release float. Alarm should stop. The audible alarm can be turned off by flipping the toggle switch on the panel front door to the left.
20. Close cover on control panel and lock if necessary.
21. In the event that a fuse blows, replace with time delay or slow blow, 125 volt minimum voltage rating and the same amp rating as the existing fuse.
22. The distribution of air to all droplines must be uniform. If the airflow is not evenly distributed, check the air pump or the main air line.
23. Spend time with your customer whenever possible. Review operation instructions. Be sure that the customer has a manual to keep. This saves valuable time avoiding return visits.
24. Retain these instructions for future reference.
25. **WARNING:** Control panel contains high voltage and must be installed and serviced only by qualified personnel.
26. **WARNING:** DF series fiberglass construction is furnished with a 24" polyethylene cover with gasket that is securely fastened to the tank lid. The cover must be placed six inches above grade to prevent surface runoff.
27. **WARNING:** DF series concrete construction is furnished with a 20" Poly-Lok[®] riser and a cover. Risers are cast into the concrete lid to ensure water tightness. The covers have gaskets and are designed for self-sealing. The cover must be placed six inches above grade to prevent surface runoff.

Delta Treatment Systems

RECOMMENDED INSTALLATION PROCEDURE

1. EXCAVATION:


Dig hole from the side for accurate sizing. This reduces the bridging distance between the tank and undisturbed soil and provides good support for inlet and outlet pipes. The bottom of the hole should be undisturbed and level. If leveling is necessary due to over excavation, use sand for fill.




NOTE: Never place tank directly on rock. place at least six inches of sand or gravel bedding between the tank and rock surface.

2. TANK PLACEMENT:

Use the back hoe to set the tank. Lifting lugs are furnished to lift the tank.



CAUTION: A small amount of soil or sand should be used around the bottom of the tank to hold it in place. Sand is best. If excavated soil is used, tamp it underneath the tank to provide a good base.



3. FILL TANK WITH WATER:

Place hose in six inch riser. Begin filling tank with water.



INSTALLATION PROCEDURE

DWN BY:
B.LANDRY

DATE:
06/23/03


SCALE:
N.T.S.

DWG. NO.:
DEP034-A

4. GFI CONTROLS AND AIR PUMP

Install duplex or quadruple GFI or GFI protected receptacles at the selected location of the air pump. Mount control panel and install fittings, tubing and piping to tank location.

CAUTION: Do not plug anything but the air pump into the control panel.




5. INLET/OUTLET AND AIR CONNECTIONS

Properly make solvent cemented inlet, outlet and air connections.

6. FILLING THE TANK


Finish filling tank with water until it drains out of outlet. Begin backfilling with natural soil or a good back fill material.



7. AIR DISTRIBUTION

Turn the air pump on and check all air connections and piping for air tightness. Observe air/water mixture through 4" riser.

NOTE: If electrical GFI receptacle has not been installed, for checking air distribution system during installation. Use an extension cord to run the air pump. Never leave the extension cord plugged in. Remove it after inspection is completed.




WARNING : Possible Fire Hazard

Do Not plug into main service equipment on power pole.

Do Not use extension cords

8. FINAL BACK FILLING

Back fill Should be mounded above grade slightly to allow for settling. Tamp the back fill beneath the inlet, outlet and air piping to provide good support.



INSTALLATION PROCEDURE

DWN BY:
B.LANDRY

DATE:
06/23/03

SCALE:
N.T.S.

DWG. NO.:
DEP034

9. TRIM INSPECTION RISERS



Trim inspection risers to proper length. The 4" aeration inspection riser also serves as a vent for the tank.

Caution: The bottom of the 4" aeration riser must be above the water level for both visual inspection and ventilation. Both of the optional 6" and 4" top caps must be above ground level to prevent ground water from entering the risers.

Caution: Care must be taken not to push the optional 6" Clarifier Inspection Riser down too far. This may cause damage to the effluent discharge tee assembly and the clarifier.

Caution: Maximum burial depth - 2 feet from top of tank flange with dome or 24" manways and 1 foot from top of tank flange with flat lids. For burial depths beyond 2 feet contact the factory.

For further details refer to the installation manual



INSTALLATION PROCEDURE

DWN BY:
B.LANDRY


DATE:
06/23/03

SCALE:
N.T.S.

DWG. NO.:
DEP034


Delta Treatment Systems Pumpout Procedure

1. Determine the amount of MLSS by using a "Sludge Judge" type sampler through the 4" vent/sample port riser.




2. Leave the air compressor for the ATU running.

3. Insert vacuum hose into the main access riser. Skim off any floatable solids on the surface of the clarifier and lower to the bottom of the clarifier.




Caution : Care must be taken not to damage the discharge tee assembly.

4. Pump out 80 to 90 percent of the ATU. Then remove the vacuum hose.



5. Insert a water hose into the main access riser. Wash down the clarifier walls and partially refill the ATU with clean water.



6. Repeat step 3 and refill the ATU with clean water.

*Never leave tank empty.

*Always use licensed pumpers/haulers for this task.



PUMP OUT PROCEDURE

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG. NO.:
DEP033

THE BASIC FOUR TROUBLESHOOTING GUIDELINES FOR TREATMENT UNIT

Is the air pump operating?
Is the air filter clean?

1. Visually inspect unit to ensure proper mechanical operation.

Visually examine inspection ports to determine if unit is receiving enough air. Is unit properly ventilated?



Is more water being used by the household than unit's design?

2. Is system being overloaded hydraulically from the household or an outside source?

Is runoff or groundwater entering the unit, pretreatment tank, dosing tank, piping?



Are there more people using the system than designed for?

3. Is system being biologically overloaded?

Are there more households on unit than designed for?



Talk with homeowner about the correct household products to use.

4. Is a toxic substance being introduced to the unit?

Talk to homeowner about garbage disposal and what waste gets dumped into sinks and drains.



Call manufacturer for further assistance.

TROUBLESHOOTING GUIDE FOR Delta Treatment Systems WHITEWATER[®] AEROBIC TREATMENT UNITS

AIR SUPPLY MALFUNCTION

1. Check to be sure all airdrops are working properly. They should be bubbling evenly and forcefully. A septic (rotten egg) odor could mean that the system is not getting enough air. If the air system is not working, partially working or working very little (slight bubbles), check the following:
 - a. Check to be sure the air pump is working.
 - check timer if one is used
 - bypass timer; temporarily connect directly to source
 - check the electrical source
 - if electrical source is OK – check service guide for pump unit troubleshooting information
 - wash air filter on pump
 - consult manufacturer for servicing information
 - b. Check to be sure tank is not severely out of level. Air follows a path of least resistance. The pressure differences at the bottom of droplines can be enough to prevent or restrict air flow.
 - c. Check for broken or cracked air lines both outside and inside the tank.
 - d. Ants will destroy an air pump. Check to see if there is an ant nest around the air pump.
 - e. Air pump should be protected from rising water.
 - f. Always check to see if inlet and outlet lines are correctly installed.

INTERNAL ASSEMBLY MALFUNCTION

1. Raw, untreated sewage from the aeration chamber (bubble zone) should not enter the clarifier (quiet zone) because of improperly installed or loose seals or gaskets where pipe goes through the clarifier wall. Check the size of holes to be sure that there is no clearance for matter to pass through the wall around the piping.
2. Check to be sure all internal piping and connections are tight.

DESIGN OVERLOAD

1. The system could be hydraulically overloaded (there is too much water going through the system for the size of the system).
2. The system could be biologically overloaded (there is too much waste for the size of the system).

IMPROPER INSTALLATION OR SETTLING

1. You should follow the manufacturer's installation procedures very carefully.
2. Where settling is common, approximately 2" of sand should be placed and tamped in the bottom of the hole.
3. Proper installation is the first step in preventing callbacks for service problems.
4. Whenever possible, it is important to spend time with the homeowners. Be sure they have an operation and maintenance manual. A few minutes invested in the beginning will avoid service calls later.

NO HARSH CHEMICALS SHOULD BE PUT INTO THE SYSTEM

1. Water in the aeration chamber (bubble zone) should be the color of chocolate milk. Blue or gray/blue water indicates heavy use of detergents or other chemicals. If water appears sudsy, there is too much detergent being used.
2. Water in the clarifier (quiet zone) should be clear, but scum and debris may appear on the surface. Water is discharged into the discharge tee at a minimum of 6–8 inches below water surface. You MAY not be able to see clear water by looking into the tank. Samples must be taken at the sample port.
3. Oils and grease should be kept to a minimum. Grease tends to form in white balls.

TROUBLESHOOTING ELECTRICAL SYSTEM

1. Air pump does not run:
 - a. Check main service for power.
 - b. Check and/or replace fuse with same rating as is in control panel.
2. Alarm does not occur when air pump is off:
 - a. Malfunctioning pressure switch – replace.
 - b. Malfunctioning light or buzzer – replace.
3. Alarm occurs continuously even when air pump is running:
 - a. Air leak in main air system or air tubing to pressure switch – repair leak or replace air line.
 - b. Malfunctioning pressure switch – replace.
 - c. High water level in tank – inspect for cause.
 - d. Short in float switch wire or float switches – repair or replace.

Note: All replacement parts are available through your local dealer.

CAUTION: Electrical shock or hazard may occur if unit is not serviced properly. The manufacturer recommends that a licensed electrician be called when electrical problems occur.

COMPONENT REPLACEMENT PROCEDURE

- **Air Pump:** Follow the same procedure as outlined in the “Installation Instructions.”
- **Float Switch:** Remove Aerobic Treatment Plant’s Riser or 24” cover. Locate float switch cable. Untie knot. Cut float switch cable. Slip float switch cable through rubber grommet into the plant. Replace with exact replacement float switch. Reinstall by reversing the procedure. Reconnect float switch wires using underground rated compound filled wire nuts. **See Float Switch Mounting Details.**
- **Pressure Switch:** Turn all power off to the control panel. Remove back plate. Remove screws securing pressure switch as well as connectors and tubing. Reverse procedure to install new pressure switch.
- **Buzzer:** Turn all power off to the control panel. Remove screw attaching the buzzer to back plate as well as connectors. Reverse procedure to install new buzzer.
- **Lamp Holder:** Turn all power off to control power. Remove lock nut securing lamp holder to door as well as connectors. Remove lamp holder. Install new lamp holder with gaskets furnished. Continue with reverse procedure.
- **Lamp:** Turn all power off to control panel. Remove red lamp cover from front of control panel. Remove and replace lamp, which is a push-in type. Replace lamp cover and cover gasket.
- **Fuse:** Turn all power off to control panel. Pull top of fuse holder outward. Remove and replace fuse. Push fuse back into place.
- **Buzzer Switch:** Turn all power off to control panel. Remove rubber boot on switch. Remove hex nut from switch on panel front as well as connectors on switch. Reverse procedure to install new switch.

GENERAL COMMENTS

- Only factory approved equipment can be used for replacement on individual treatment systems.
- If the decision is made to pump out a system, be sure to contact a licensed waste-hauler.
- If a chronic problem develops and all items have been checked, consult with the factory.
- **A properly operating unit will produce a clear, odorless discharge; the mixed liquor in the aeration tank should be a medium brown color with good settling features and have an earthy smell.**
- Keep good records.

Note: If the entire cover needs to be removed on any one of the various model treatment plants, the existing silicone or strip seal must be removed and replaced with a new one. This will provide a positive seal that will not allow any infiltration into or out of the treatment plant.

APPENDIX A

SPECIFICATIONS, DIMENSIONS AND TREATMENT PLANT DRAWINGS

SPECIFICATIONS

TREATMENT PLANT	TREATMENT CAPACITY (GPD)	TOTAL VOLUME (GAL.)	AERATION VOLUME (GAL.)	CLARIFIER VOLUME (GAL.)	BOD LOADING (LBS./DAY)	NO. OF AIR DROPS
DF40	400	764	596	168	1.00	5
DF50	500	909	720	189	1.25	5
DF50A	500	925	732	193	1.25	5
DF60	600	1147	867	280	1.5	6
DF75	750	1438	1100	338	1.88	6
DF100	1000	1926	1470	456	2.5	8
DF100A	1000	1926	1429	497	2.5	8
DF100B	1000	2191	1759	432	2.5	8
DF150	1500	2882	2227	655	3.75	8

MATERIALS OF CONSTRUCTION:

Suffix M	Aeration Tank	Steel
	Cover	Steel
	Clarifier	Fiberglass
Suffix F & FF*	Aeration Tank	Fiberglass
	Cover	Fiberglass
	Clarifier	Fiberglass
Suffix C	Aeration Tank	Concrete
	Cover	Fiberglass
	Clarifier	Fiberglass
Suffix CA* & CC	Aeration Tank	Concrete
	Cover	Concrete
	Clarifier	Fiberglass

***Standard Production Units. Other configurations are available upon special request.**

PARTS LIST	ITEM	MATERIALS OF CONSTRUCTION
Aeration Tank	1.	See Above
Clarifier	2.	See Above
Air Distribution System	3.	PVC
Access Cover	4.	Polyethylene
Discharge Piping Assembly	5.	PVC
Air Pump Assembly	6.	See Air Pump Parts List
Sample Port	7.	PVC
Control Panel	8.	NEMA 3R Steel or NEMA 4X Fiberglass
High Water Float Switch	9.	Polyethylene

ELECTRICAL REQUIREMENTS


Model	Compressor	Motor Full Load Amps	Measured Operating Watts	Electrical Requirements
DF-40	5060A	1.75	63	115 volt – single phase
	Delta Model 60	1.75	63	
	D60	1.75	63	
DF-50	5060A	1.75	63	115 volt – single phase
	5078S	2.1	85	
	AT03	4.0	391	
	Delta Model 60	1.75	63	
	D60	1.75	63	
	Delta Model 80	2.1	85	
	D80	2.1	85	
DF-60	5078S	2.1	85	115 volt – single phase
	AT05	4.6	449	
	5100S	2.71	110	
	Delta Model 80	2.1	85	
	D80	2.1	85	
	Delta Model 100	2.71	110	
	D100L	2.71	110	
DF-75	5100S	2.71	110	115 volt – single phase
	5120S	2.8	157	
	5078S	2.1	85	
	AT05	4.6	449	
	Delta Model 100	2.71	110	
	D100L	2.71	110	
	Delta Model 120	2.8	157	
	D120L	2.8	157	
DF-100	(1) 0823	(1) 10.4	(1) 640	115 volt – single phase
	(2) Delta Model 80	(2) 2.1	(2) 85	
	(2) D80	(2) 2.1	(2) 85	
DF-150	(3) 5100S	(3) 2.71	(3) 110	115 volt – single phase
	(1) 1023	(1) 10.4	(1) 850	
	(2) 5120S	(2) 2.8	(2) 157	
	(3) Delta Model 100	(3) 2.71	(3) 110	
	(3) D100L	(3) 2.71	(3) 110	
	(2) Delta Model 120	(2) 2.8	(2) 157	
	(2) D120L	(2) 2.8	(2) 157	

DIMENSIONS


TREATMENT PLANT	A	B	C	D	E	F	G	H
DF40	4' 11-3/16"	4' 8-3/16"	5' 6"	4' 5-9/16"	5' 0"	10"	6' 0"	10"
DF50	4' 11-3/16"	4' 8-3/16"	6' 0"	4' 5-9/16"	5' 0"	10"	6' 6"	10"
DF50A	5' 10-3/16"	5' 7-3/16"	5' 6"	5' 4-9/16"	5' 11"	10"	6' 0"	10"
DF60	5' 7-3/4"	5' 4"	6' 3"	5' 1-1/2"	5' 9"	11-1/2"	6' 9"	10"
DF75	6' 0-1/2"	5' 8-1/2"	6' 9"	5' 6"	6' 2"	11-1/2"	7' 3"	10"
DF100	6' 5-5/8"	6' 2"	7' 6"	5' 11-1/2"	6' 8"	1' 0"	8' 0"	10"
DF100A	5' 9-5/8"	5' 6"	8' 0"	5' 3"	6' 0"	1' 0"	8' 6"	10"
DF100B	6' 5-5/8"	6' 2"	8' 0"	5' 11-1/2"	6' 8"	1' 1"	8' 6"	10"
DF150	8' 3-5/8"	8' 0"	8' 0"	7' 9-1/2"	8' 6"	1' 3-3/4"	8' 6"	10"

Refer to treatment plant drawings on the above dimensions.

Note: For special cargo or container shipments 12 inches must be added to the diameters of all fiberglass units (due to the fiberglass flange and lifting lugs).



Plan View
(with cover removed)



Section



FLOW DIAGRAM TREATMENT PLANTS


DWN BY:
B.LANDRY

DATE:
06/19/03


SCALE:
N.T.S.

DWG. NO.:
CRT600



Note: See dimension sheet for number of air drops



Plan View
(with cover removed)



Alternate Access Port



Section A-A

* HIGH LEVEL FLOAT NOT REQUIRED
WHEN USING CP22 SERIES CONTROL PANELS



WASTEWATER TREATMENT UNITS MODEL DFX-M


DWN BY:
B.LANDRY

DATE:
06/19/03

SCALE:
N.T.S.

DWG. NO.:
CRT601

Note: See dimension sheet for number of air drops




WASTEWATER TREATMENT UNITS MODEL DFXX-F

DWN BY:
B.LANDRY





DATE:
06/19/03

SCALE:
N.T.S.

DWG. NO.:
CRT602



Plan View
(with cover removed)



Section A-A

* HIGH LEVEL FLOAT NOT REQUIRED
WHEN USING CP22 SERIES CONTROL PANELS



WASTEWATER TREATMENT UNITS MODEL DFXX-FF


DWN BY:
B.LANDRY

DATE:
06/19/03

SCALE:
N.T.S.

DWG. NO.:
CRT603

Note: See dimension sheet for number of air drops



* HIGH LEVEL FLOAT NOT REQUIRED WHEN USING CP22 SERIES CONTROL PANELS



WASTEWATER TREATMENT UNITS MODEL DFXX-C


DWN BY:
B.LANDRY

DATE:
06/19/03

SCALE:
N.T.S.

DWG. NO.:
CRT604

Note: See dimension sheet for number of air drops




* HIGH LEVEL FLOAT NOT REQUIRED WHEN USING CP22 SERIES CONTROL PANELS



WASTEWATER TREATMENT UNITS MODEL DFXX-CA

DWN BY: B.LANDRY	DATE: 06/19/03	SCALE: N.T.S.	DWG. NO.: CRT605
---------------------	-------------------	------------------	---------------------

Note: See dimension sheet for number of air drops



WASTEWATER TREATMENT UNITS MODEL DFXX-C

DWN BY:
B.LANDRY

DATE:
06/19/03


SCALE:
N.T.S.

DWG. NO.:
CRT604


APPENDIX B

ELECTRICAL DRAWINGS

DIRECT AIRLINE TAP INSTALLATION METHOD




COMPRESSOR AIRLINE TAP INSTALLATION METHOD



TUBING CONNECTION ASSEMBLY DRAWING

DWN BY:	DATE:	SCALE:	DWG. NO.:
BLANDRY	04/29/04	N.T.S.	DEP005

CP23 CONTROL PANEL



SETTING HIGH LEVEL PRESSURE SWITCH

BRING PLANT TO OPERATING WATER LEVEL WITH COMPRESSOR TURNED ON. USING PROPERLY SIZED SCREW DRIVER, TURN HIGH LEVEL ALARM ADJUSTMENT SCREW CLOCKWISE UNTIL ALARM OCCURS. THEN TURN THE SCREW COUNTER-CLOCKWISE UNTIL ALARM STOPS.



CONTROL PANEL CONNECTIONS MODEL CP 23

DWN BY:

B.LANDRY

DATE:


06/19/03

SCALE:

N.T.S.

DWG. NO.:

CRT305




CP 23 CONTROL PANEL CONNECTIONS USING QR SERIES COMPRESSORS

DWN BY:
B.LANDRY

DATE:
07/17/03

SCALE:
N.T.S.

DWG. NO.:
DEP044



SCHEMATIC DIAGRAM
CP23

* SIZE VARIES WITH
COMPRESSOR SIZE PER
NATIONAL ELECTRICAL CODE




SCHEMATIC DIAGRAM
CP 23

DWN BY:
B.LANDRY

DATE:
06/19/03

SCALE:
N.T.S.

DWG. NO.:
CP23



FS1-FLOAT SWITCH IN TREATMENT PLANT
 * FUSE SIZE VARIES WITH COMPRESSOR SIZE
 PER NATIONAL ELECTRIC CODE

FRONT VIEW
 DOOR OPEN
 CP20




CP20 PANEL

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG. NO.:
CP20



SCHEMATIC DIAGRAM
CP20 SERIES

* FUSE SIZE VARIES WITH COMPRESSOR SIZE
PER NATIONAL ELECTRICAL CODE




CP20 WIRING DIAGRAM

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG. NO.:
CP20



FRONT VIEW
DOOR OPEN
CP22

FS1-FLOAT SWITCH IN TREATMENT PLANT
* FUSE SIZE VARIES WITH COMPRESSOR SIZE
PER NATIONAL ELECTRIC CODE




CP 22 PANEL

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG.NO.:
CP22P



SCHEMATIC DIAGRAM

CP22 SERIES

FS1- H.L. FLOAT SWITCH (OPTIONAL)

* FUSE SIZE VARIES WITH COMPRESSOR SIZE
PER NATIONAL ELECTRICAL CODE

-A SEPERATE DISCONNECT IS REQUIRED.

DWG . CP22





CP 22 WIRING DIAGRAM

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG.NO.:
CP22





CONTROL PANEL CONNECTIONS USING ROTARY SERIES COMPRESSORS

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG. NO.:
CRT610




CONTROL PANEL CONNECTIONS USING LINEAR COMPRESSOR

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG. NO.:
CRT609



NOTES:

1. GROMMET TO BE SELECTED FOR TIGHT FIT AROUND CABLE AND IN LID.
2. WIRE TO CONTROL PANEL TO BE 18 GAUGE AND RATED FOR DIRECT BURIAL SERVICE. WOODS WIRE-886 OR EQUAL.
3. WIRE NUTS TO BE RATED FOR UNDERGROUND SERVICE IDEAL-DB PLUS MODEL 60 OR EQUAL.
4. FLOAT SWITCH TO BE NORMALLY OPEN MDI-AS10Y0500 OR EQUAL.
5. SMALL ACCESS PORT SHOWN ON DRAWING LARGE ACCESS PORTS MAY BE SUPPLIED.
6. MINIMUM AMOUNT OF CONDUIT SHOWN ABOVE IS REQUIRED EVEN WITH TYPE UF CABLE.



FLOAT SWITCH MOUNTING

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG. NO.:
CRT611

ADDITIONAL MATERIALS NEEDED FOR CONTROL PANEL ELECTRICAL INSTALLATION


<u>QUANTITY</u>	<u>ITEM</u>	<u>MANUFACTURER OR EQUAL</u>
As required	2#12UF with ground	
2	300 volt silicon filled underground service wire nuts	King-6T
As required	Conduit and fittings are as shown in the drawings contained in this manual.	
1	20 amp minimum A/C type disconnect switch or equal. Required on CP20 series panels only	

APPENDIX C


AIR PUMP DRAWINGS AND PARTS LIST

DRAWINGS


5078S, 5100S-C, 5120S, 5150S, 5200S



5030-A, 5040-A, 5060-A and V models



5006, 5015, 5020 and V models



PARTS LIST

Part Number	Description	Model
C50141	Shuttle assembly	5006, 5015, 5020 (Plus MO, SE and V models)
C50279	Service kit (2 required)	5006, 5015, 5020 (Plus MO, SE and V models)
C50144	L-tube (2 required)	5006, 5015, 5020 and V models
C50283	Gasket, tank	5006, 5015, 5020 and V models
C50151	Shuttle assembly	5030-A, 5040-A and V models
C50401-P	Service kit	5030-A, 5040-A and V models
C50554	L-tube (2 required)	5030-A, 5040-A, 5060-A and V models
C56008	Gasket, tank	5030-A, 5040-A, 5060-A and V models
C56300	Air filter	5030-A, 5040-A, 5060-A and V models
C50159	Shuttle assembly	5060-A and V models
C50397-P	Service kit	5060-A and V models
C50272	Shuttle assembly	5078S
C50284	Gasket, tank	5078S, 5100S-C, 5120S
C50318	Air filter	5078S, 5100S-C, 5120S
C53900	L-tube (2 required)	5078S, 5100S-C, 5120S
C56002	Gasket, filter cover	5078S, 5100S-C, 5120S
C50402-P	Service kit	5078S, 5100S-C, 5120S
C51600	Shuttle assembly	5100S-C, 5120S
C50265	Shuttle assembly	5150S, 5200S
C50285	Gasket, tank	5150S, 5200S
C53903	L-tube (2 required)	5150S, 5200S
C56005	Gasket, filter cover	5150S, 5200S
C56302	Air filter	5150S, 5200S
C50403-P	Service kit	5150S, 5200S

Note: Service kits (except C50279) include base gasket, filter cover gasket (where appropriate), L-tubes (2), head and diaphragm assembly (2) and intake filter. Service kit C50279 includes head and diaphragm assembly (2) only.

PARTS LIST

QR-0030

QR-0050

QR-0080


QR-0100

REF. NO.	DESCRIPTION	PART QTY.	291305 QR-0030	291306 QR-0050	291303 QR-0080	291304 QR-0100
1	SILENCER	1	C60362		C60363-P	
2	VANE KIT [(4) VANES, GASKET]	1	L32100-P		L32103-P	
3	ENDPLATE	1	L07163		L07166	
4	SOUND CHAMBER	1	L07164		L07165	
5	GASKET	1	L31058		L31059	
6	SHROUD	1	L38230		L38231	
7	FILTER KIT [(8) FELTS, (2) O-RINGS]	1	L84194-P		L84195-P	
8	MOTOR	1	L36236		L36235	
—	SHIM .0010 THICK	A/R*	L10556		L10569 (.0010)	
—	SHIM .0015 THICK	A/R*	L10557		L10570 (.0015)	
—	SHIM .0020 THICK	A/R*	L10558		L10571 (.0020)	

*AS REQUIRED

EXPLODED VIEW


QR-0030 QR-0050
QR-0080 QR-0100



HP SERIES

STRUCTURE AND PARTS NAMES

Air pump	Start of production	Discontinuance of production
HP-60	1995/ 9	—
HP-80	1995/ 9	—




HP-60/80

- ① Filter Cover
- ② Semi Cover Packing
- ③ Filter
- ④ Fitting Boss
- ⑤ Upper Housing
- ⑥ Sound Absorber
- ⑦ Casing Block
- ⑧ Diaphragm Ring
- ⑨ Diaphragm
- ⑩ Diaphragm Base
- ⑪ SP Switch
- ⑫ Safety Screw
- ⑬ Electromagnet
- ⑭ Actuating Rod
- ⑮ L-Tube
- ⑯ Hose Band
- ⑰ Frame
- ⑱ Vibration Control Rubber
- ⑲ Center Plate
- ⑳ Gasket
- ㉑ Lower Housing
- ㉒ Power Cord

HP SERIES

STRUCTURE AND PARTS NAMES

Air pump	Start of production	Discontinuance of production
HP-100	1997/10	—
HP-120	1997/10	—



HP-100/120

- ① Filter Cover
- ② Semi Cover Packing
- ③ Filter
- ④ Fitting Boss
- ⑤ Upper Housing
- ⑥ Sound Absorber (Lap)
- ⑦ Casing Block A
- ⑧ Valve Chamber Packing
- ⑨ Casing Block B
- ⑩ Valve
- ⑪ Diaphragm Ring
- ⑫ Diaphragm
- ⑬ Diaphragm Base
- ⑭ Frame Cover
- ⑮ SP Switch
- ⑯ Safety Screw
- ⑰ Electromagnet
- ⑱ Actuating Rod
- ⑲ L-Tube
- ⑳ Hose Band
- ㉑ Frame
- ㉒ Vibration Control Rubber
- ㉓ Center Plate
- ㉔ Gasket
- ㉕ Sound Absorber (Filter)
- ㉖ Lower Housing
- ㉗ Power Cord

EXPLODED PRODUCT VIEW, PARTS & ORDERING INFORMATION


REF	DESCRIPTION	QTY	0323-101	0323-101Q	0523-101	0523-101Q	0523-V103
1	BODY	1	AK503	AK503	AK505	AK505	AK505
2 *	VANE	4	AH850A	AH850A	AH850A	AH850A	AH850A
3	SHROUD	1	AK502	AK502	AK502	AK502	AK502
4	END PLATE	1	AK516A	AK501	AK516A	AK501	AK516A
5 *	GASKET	1		AK521		AK521	
6	MUFFLER BOX	1		AK519		AK519	
7 *	O-RING	2		AK473		AK473	
8 *	FELT	2		AK524		AK524	
9	END CAP	2		AK510		AK510	
10	END CAP ASSEMBLY	2		AK526		AK526	
11	FILTER / MUFFLER	1		AK840A		AK840A	
12	FOOT SUPPORT	1		AC136		AC136	
13	ELBOW ***	2					AD997
14	MUFFLER ASSEMBLY	1					V425L
15	JAR	2					AA125A
16	COVER	1					AV427A
17	FELT FILTER	4					B344A
18	SUPPORT	1					B345A
19	COVER GASKET	2					B62A
20	FILTER ASSEMBLY	1					V400G
21	COVER	1					AV402C
22	FILTER ASSEMBLY	1					B343B
23	SCREEN CAP	1					AJ571
24	FELT SUPPORT	1					B347
	SERVICE KIT	1	K478A	K478	K478A	K478	K559

* Denotes parts included in the Service Kit. Parts listed are for stock models.

** No Service Kit available, order parts separately. *** Not shown.

For specific OEM models, please consult the factory.

When corresponding or ordering parts, please give complete model and serial numbers.




REF	DESCRIPTION	QTY	0823-101	0823-101Q	1023-101	1023-101Q	1023-V103	1423-101Q
1	BODY	1	AK517	AK517	AK518	AK518	AK518	AL283
2 *	VANE	4	AK513	AK513	AK513	AK513	AK513	AL284
3	SHROUD	1	AK511	AK511	AK511	AK511	AK511	AL281
4	END PLATE	1	AK515A	AK514	AK515A	AK514	AK515A	AK514
5 *	GASKET	1		AK522		AK522		AK522
6	MUFFLER BOX	1		AK520		AK520		AK520
7 *	O-RING	2		AK473		AK473		AK473
8 *	FELT	2		AK524		AK524		AK524
9	END CAP	2		AK510		AK510		AK510
10	END CAP ASSEMBLY	2		AK526		AK526		AK526
11	FILTER / MUFFLER	1		AK840		AK840		AC432
12	ELBOW	1						BA206
12	ELBOW ***	2					AF272	
13	MUFFLER ASSEMBLY	1					AB599B	
13a	NIPPLE	2						BA714
14	JAR	2					AA805	
15	COVER GASKET	2					AA405	
16	COVER ASSEMBLY	1					AV805B	
17	MUFFLER ASSEMBLY	1					AC434-1	
18	COUPLING	2					AC391	
19	CARTRIDGE	2					AC393	
20	END CAP ASSEMBLY	2					AC394	
21	MUFFLER PLATE	1					AC395	
22	STUD	2					AC396	
23	FILTER ASSEMBLY	1					AB599	
24	COVER ASSEMBLY	1					AV805APC	
25	FILTER ASSEMBLY	1					AC433-1	
	SERVICE KIT	1	K479A	K479	K479A	K479	K479A	K575A

* Denotes parts included in the Service Kit. Parts listed are for stock models.


** No Service Kit available, order parts separately. *** Not shown.

For specific OEM models, please consult the factory. When corresponding or ordering parts, please give complete model and serial numbers.


For 1423 Models only.
(Shipped unattached)



Vacuum Intake
Filter Assembly




Muffler
Assembly



AP SERIES

STRUCTURE AND PARTS NAMES



1 - Air Filter 641811

2 - Air Filter Cover Gasket 639571

3 - Chamber Block (2 each included in service kit SK-AP60/8)



4 - Diaphragm Assembly (2 each included in service kit SK-AI)

5 - Tank Gasket 639572

APPENDIX D NAMEPLATES

TREATMENT PLANT DATA PLATES

4"			
WHITEWATER Delta Treatment Systems 925 Comer Drive Walker, LA 70785 Phone: 1-800-219-9183 Model DF XXX-X NSF/ANSI STD 40 XXX GPD Class I Serial No. XX-XXXXX XX NSF		2"	
4"			
ALARM MALFUNCTION ELECTRICAL PANEL WHITEWATER Delta Treatment Systems 925 Comer Drive Walker, LA 70785 Phone: 1-800-219-9183 Model DF XXX-X NSF/ANSI STD 40 XXX GPD Class I Serial No. XX-XXXXX XX NSF		3"	



* HIGH LEVEL FLOAT REQUIRED
WHEN USING CP22 SERIES CONTROL PANELS

NAME PLATE DATA

NP1

1-800-219-9183

NP2

MODEL DFXX-X
XXXX GPD
ANSI/NSF STD 40
CLASS 1
SERIAL NO. XXXXX



ALTERNATE ACCESS PORT MODEL DFXX-X

DWN BY:
B.LANDRY

DATE:
04/09/03

SCALE:
N.T.S.

DWG. NO.:
CRT613

APPENDIX E
SERVICE POLICY, WARRANTIES
AND INSPECTION COUPONS

DELTA TREATMENT SYSTEMS INDIVIDUAL MECHANICAL WASTEWATER TREATMENT SYSTEM SERVICE POLICY

INITIAL POLICY:

A two-year initial service policy shall be furnished to the user by the manufacturer or the distributor through the dealer. This policy is to be included in the purchase price from the seller of the system and shall provide the following:

1. **An inspection/service call every six months**, which includes inspection, adjustment and servicing of the mechanical and electrical component parts as necessary to ensure proper function.
2. An effluent quality inspection every six months consisting of a visual check for color, turbidity, scum overflow and an examination for odors.
3. If any improper operation is observed which cannot be corrected at that time, the user shall be notified immediately in writing of the conditions and the estimated date of correction. **THIS POLICY DOES NOT INCLUDE PUMPING SLUDGE FROM UNIT IF DEEMED NECESSARY.**

CONTINUING SERVICE POLICY:

An annually renewable service policy affording the same coverage as the Initial Service Policy is available. Consult your dealer for pricing information.

PARTS:

Replacement parts or components may be obtained from your local distributor or contact Delta Environmental for information.

COMPLAINTS:

In order for Delta Environmental to properly address complaints, we require that you put in writing the date and nature of the complaint as detailed as possible. This must include the serial number of your system.

Send to: Delta Environmental
625 Comer Drive
Walker, LA 70785

THIS PAGE INTENTIONALLY LEFT BLANK

THIS PAGE INTENTIONALLY LEFT BLANK

THIS PAGE INTENTIONALLY LEFT BLANK

LIMITED WARRANTY

Delta Treatment Systems warrants the parts in each treatment system as follows: linear air pump: limited pro-rated five (5) years – first two (2) years 100%, third (3) year 75%, fourth (4) year 50%, fifth (5) year, 25%. The 3, 4, and 5 year pro-rated portion of this warranty is valid only with a continuing Service Policy in effect. Proof of this continuing Service Policy must be provided. Rotary compressor

– limited two (2) years, fiberglass tanks: limited two (2) years, and concrete tanks: limited two (2) years. All warranty questions shall be resolved through Delta Treatment Systems. The warranty on the treatment device is that the device is free from defects in material and workmanship from the date of installation treating household wastewater. Some states do not allow limitations on how long an implied warranty lasts, so the above limitation may not apply. Sole obligation under this warranty is as follows: Delta Treatment Systems shall fulfill this warranty by repairing or exchanging any component part, F.O.B. factory that in Delta Treatment Systems judgment shows evidence of defects, provided said component part has been paid for and is returned through an authorized dealer, transportation prepaid. The warrantee must also specify the nature of the defect to the manufacturer.

The warranty does not cover treatment processes/devices that have been flooded, by external means, or that have been disassembled by unauthorized persons, improperly installed, subjected to external damage or damaged due to altered or improper wiring or overload protection.

This warranty applies only to the treatment process/device and does not include any of the house wiring, plumbing, drainage, or disposal system. Delta Treatment Systems is not responsible for any delay or damages caused by defective components or material, or for loss incurred because of interruption of service, or for any other special or consequential damages or incidental expenses arising from the manufacture, sale or use of this process/device.

Delta Treatment Systems reserves the right to revise, change or modify the construction and design of the treatment process/device for household wastewater or any component part or parts thereof without incurring any obligation to make such changes or modifications in previously sold equipment. Delta Treatment Systems also reserves the right, in making replacements of component parts under this warranty, to furnish a component part which, in its judgment is equivalent to the part replaced.

Under no circumstances will Delta Treatment Systems be responsible to the warrantee for any other direct or consequential damages, including but not limited to lost profits, lost income, labor charges, delays in production, and/or idle production, which damages are caused by a defect in material and/or workmanship in its parts. Some states do not allow the exclusion of limitation of incidental or consequential damages, so the above limitation or exclusion may not apply to you.

This warranty is expressly in lieu of any other express or implied warranty, excluding any warranty of merchantability or fitness and of any other obligation on the part of Delta Treatment Systems.

This warranty gives you specific legal rights, and you may also have other rights which vary from state to state.

Rev. 4/2018

Delta Treatment Systems
9125 Comer Drive
Walker, LA 70785
1-800-219-9183